

Drawing notes

- 1) Mansfield willow run Lavatory to be installed and water tested
- 2) Radiator is a Stelrad K10820
- 3) Shower valve is a Waltec 14F625-1
- 4) Finished wall is Plywood
- 5) Steel pipe to be 100mm off wall
- 6) copper pipe to be 60mm off wall
- 7) Lav waterlines Hot and Cold to be stubbed out 64mm from plywood to $\frac{3}{8}$ " compression outlet
- 8) Rad will be roughed in at $2\frac{5}{8}$ " off wall
- 9) Bottom of rad to be 150mm off finished floor
- 10) Rad to have isolation valves installed
- 11) Hot waterlines to be installed using Press fit fittings
- 12) Cold waterlines to be soldered
- 13) DWV 90 to be centered on finished floor

