

# Drawing notes

- 1) Mansfield willow run Lavatory to be installed and water tested
- 2) Radiator is a Stelrad K11220
- 3) Shower valve is a Delta R10000-UN
- 4) Finished wall is Plywood
- 5) Heating pipes to be 100mm off wall
- 6) Domestic copper pipes to be 60mm off wall
- 7) Lav waterlines Hot and Cold to be stubbed out 64mm from plywood to  $\frac{3}{8}$ " compression outlet
- 8) Rad will be roughed in at  $2\frac{5}{8}$ " off wall
- 9) Bottom of rad to be 150mm off finished floor
- 10) Rad to have isolation valves installed
- 11) Hot waterlines to be installed using Press fit fittings
- 12) Cold waterlines to be soldered
- 13) DWV 90 to be centered on finished floor
- 14) All other dimensions can be found on shop drawings
- 15) All measurements shall be taken from Datum lines which must be marked clearly
- 16) The 45's on the domestic offset shall be bent
- 17) Heating lines must be complete by end of day 1

